



















**K1 - KOSI KROV**

- obloga krova - biber crijep 1,5 cm
- potkonstrukcija obloge - drvene kontraletve 4/6 cm 4x4 cm
- zračni sloj / potkonstrukcija obloge - drvene letve 4/6 cm 4 cm
- parna brana 0,02 cm
- drveni rog / mineralna vuna 16 cm
- gips-kartonске ploče u dva sloja 2x1,25 cm

**Z1 - VANJSKI ZID JEDINICE - GRIJANI PROSTOR**

- zidna obloga jedinice - biber crijep 1,5 cm
- potkonstrukcija obloge - drvene kontraletve 4/6 cm 4 cm
- zračni sloj / potkonstrukcija obloge - drvene letve 4/6 cm 4 cm
- mineralna vuna 15 cm
- armiranobetonski zid 20 cm
- unutarnja žbuka + boja 2 cm

**Z2 - VANJSKI ZID JEDINICE - PODNOŽJE ZGRADE - GRIJANI PROSTOR**

- produžna žbuka 2 cm
- armiranobetonski zid 16 cm
- sintetska izolacijska traka (TPO ili sl.) sa staklenom voalom s donje strane 0,4 cm
- toplinska izolacija - ekstrudirani polistiren XPS 12 cm
- betonski prefabrikat 8 cm

**P1 - POD NA TLU - JEDINICA - GRIJANI PROSTOR**

- linoleum+punoplošno ljepilo (varenje spojeva) 2,5 mm
- nivelir masa 3 mm
- parna brana 0,02 cm
- armirani plivajući cementni estrih 8 cm
- polietilenska folija 0,02 cm
- pjenasta PE folija , za prigušenje udarnog zvuka 0,5 cm
- toplinska izolacija - ekstrudirani polistiren XPS, s rubnim preklopima, u dva sloja 16 cm
- armiranobetonska ploča ≥ 20 cm
- sintetska izolacijska traka (TPO ili sl.) sa staklenom voalom s donje strane 0,4 cm
- zaglađena betonska podloga, lagano armirana 10 cm
- nabijeni šljunak 15 cm

